Wisco Moran Drilling Company



<u>DRAWWORKS</u>: INGERSOLL-RAND (IRI) 1200 SERIES TRAILER MOUNTED RIG WITH IRI 2550 MECHANICAL DRAWWORKS WITH TWIN PARMAC V-80 HYDROMATIC BRAKES

ENGINES: TWO (2) CAT 3412DITA ELECTRONIC CONTROLLED DIESEL ENGINESRATED 750HP EACH AT 2100 RPM WITH ALLISON MODELS6600 TRANSMISSIONS, COMPLETE WITH HYDRAULIC CONTROLS, POWERING THE 1500 HP DRAWWORKS

MAST: IRI 136'MAST WITH 700,000# HOOKLOAD. MAST HAS CAPABILITY TO ACCOMMODATE A 700 HP TOP DRIVE

SUBSTRUCTURE: IRI22' TELESCOPING SUBSTRUCTURERATED AT 700,000# ROATARY LOAD WITH 400,000# SIMULTANEOUS SETBACK

TOP DRIVE: TESCO 250 HXI 700 TOPDRIVE AND POWER UNIT, RATED 700HP, 250 TON, (2) SPEED/TORQUE RANGES, 24,000# MAX CONTINUOUS TORQUE W/MAX 100RPMAND 12,000#MAXCONTINOUSTORQUE W/MAX 200 RPM

MUD PUMPS: TWO (2) NATIONAL 10-P-130 (1,300 HP) POWERED BY 1-GE 752 (HT) TRACTION MOTOR.

RIG NO. 16- INVENTORY OF EQUIPMENT

WELLCONTROL: 1-11" 10 M CIW "TYPE U" DOUBLE BOP FLANGED. 1-11" 10 M CIW "TYPEU" SINGLEBOP FLANGED. 1- 11" 5M SHAFFER SPHERICAL ANNULAR BOP. 1- 3" 10 M CHOKE MANIFOLD. 1-CIW 13 5/8 5M TYPE "U" DOUBLE BOP, SHAFFER 13 5/8 5M SPHERICAL BOP. 1-11" 10M DRILLING SPOOL WITH 3" 10M OUTLETS. 1- 13 5/8 5M DRILLING SPOOL WITH 4" 5M OUTLETS.

ACCUMULATOR: KOOMEY TYPE 80 (5) FIVE STATION CLOSING UNIT, WITH (16) 11 GALLON ACCUMULATOR BOTTLES,1()TRIPLEX PUMP, (2) AIR PUMPS WITH 120:1 RATIO

<u>MUD</u> <u>SYSTEM:</u> TWO (2) TANK MUD SYSTEM OF APPROXIMATELY BBLS TOTAL CAPACITY WITH 5 AGITATORS 100 BBL PREMIX PIT BUILT INTO SUCTION.

SHALE SHAKERS-TWO (2) DERRICK FLC-503, DESANDER- DERRICK DSV-10-2 (2-12" CONES), DESILTER DERRICKS-412-S

(12-4" CONES)

TRIP TANK: 100 BARRELS

<u>GENERATORS</u>: 3-1250 KW 600 VOLT GENRATORS POWERED BY 3 MTU-4000 DIESEL ENGINES.

SCR HOUSE: ROSS HILL 1400 SCR 3 GEN

BLOCK/HOOK:360TON,6 SHEAVE, TRAVELING BLOCKANDONE350TON HOOK. 1 1/4" DRILLING LINE

ROTARY TABLE: CE 27 1/2" W/HYDRAULIC MOTOR

WATERTANK:470 BBL COMPLETE W/(2)3"x 2" SERIES 250 CENTRIFUGAL WATER PUMPS POWERED BY 20 HP AC ELECTRIC MOTORS

FUELTANK: 12,000 GALLON W/(2)ROPER 3HP FUEL TRANSFER PUMPS

DRILLERSDOGHOUSE: DSI 10'X 20'

AUXILIARY EQUIPMENT: TWO (2) PC12 HYDRAULIC WINCHES, (1) IRK AIRHOIST, SPINMASTER HYDRAULIC

INSTRUMENTATION: WEIGHT INDICATOR, W/TONG LINE PULL, PUMP PRESSURE & ROTARY TORQUE GAUGES, TYPE "D" 5,000 PSI MUD PRESSURE GAUGE

WELL SITE TRAILERS: RIG MANAGER TRAILER 54' X 12'6"X 11'8", CREW CHANGE HOUSE